



VIA EMAIL ONLY

March 17, 2023

2023 EMERGENCY SERVICES WATER/SANITARY UTILITY

BOROUGH OF ROSELAND

ESSEX COUNTY, NEW JERSEY

Our File No. RL-171

ADDENDUM NO. 1

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated February 28, 2023. Acknowledge receipt of the Addendum on the proposal form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of two (2) pages.

ADDENDUM NO. 1 – TECHNICAL SPECIFICATIONS

1. Add the following to Section 01150 'MEASUREMENT AND PAYMENT':

Initial Backfill Material, Complete in Place (Item 2)

Measurement for initial backfill material shall be made in cubic yards for the actual number of cubic yards in place and to such widths, depths and lengths as directed by the Engineer.

Payment for initial backfill material shall be made at the unit price bid per cubic yard in the proposal, which price and payment shall be full compensation for all costs of material, equipment and labor required to import select fill and dispose of unsuitable trench material as determined by the Engineer.

Installation and compaction of initial backfill material shall be included in the unit price bid in this item. Initial backfill material shall cover 24" from the top of pipe and placed in 6" tamped layers. The use of heavy compacting equipment is prohibited. The initial backfill material shall be sand, gravel or loose soil free from rocks or debris.

Placement of initial backfill material shall conform to the requirements of Section 02221, EXCAVATION, BACKFILLING AND COMPACTING.

Initial backfill material shall be used as additional material as required and to replace unsuitable material as determined by the Engineer.

Any combination of materials to be used as initial backfill material shall not entitle the Contractor to additional compensation. No penalty shall be incurred for additions or deletions of material based on actual field conditions.

END OF ADDENDUM NO. 1